

STILLSTACK · DESIGN DECISION RECORD

StillStack design for construction

Design Molecule Lab · designmolecule.com

DOCUMENT CONTROL

Document ID	SSK-DDR-003	Version	0.1
Status	Draft	Date	2026-10-01
Author	Amish Chadha	License	CERN-OHL-S-2.0
Project TRL	TRL 3 Proof of concept		
Repository	github.com/BoujeeEnjinia1701/stillstack		
Source	docs/decisions/0003-design-for-construction.md @ uncommitted		

REVISION HISTORY

Version	Date	Author	Change
0.1	2026-10-01	Amish Chadha	Changes that make the concept physically buildable, with the reason for each; made under Amish's 2026-09-30 instruction to make the design physically buildable; open for his review

0003: Design for construction

- **Date:** 2026-10-01
- **Status:** Draft. The changes in Table 1 were made under Amish's 2026-09-30 instruction to make the design physically buildable; open for his review. The items in Table 3 change the safety case or what the panel does, so they are **Proposed, awaiting Amish**; the model and the build plan show the recommended option.

■ Context

On 2026-09-30 Amish asked for a build plan that shows how each component is made and how it fits the next, and wrote: "If you are realising that the design cannot be built as per concept - fix the design assumptions to match and be physically feasible as you draw the illustrations." The concept model (SSK-DDR-002) showed what StillStack does but left several parts that could not be made, fixed or assembled as drawn. Checking the model with build123d found twelve (P1 to P12 below).

The changes keep what the panel does: the same 1 m2 aperture, four stages with 6 mm gaps, plate and wick materials, ribs at 194 mm pitch, 25 mm air gap and twin-wall glazing, air-cooled fins, gravity feed from a trough at the high edge, a lidded distillate manifold and a brine gutter outboard of and lower than it at the low edge, and a stand adjustable from 10 to 35 deg. Every change is in `cad/src/model.py`, which now runs 93 constructability checks (`python cad/src/model.py --check`): no overlaps among the 46 panel parts, every contact that must exist does, every brine path keeps 10 mm from every distillate path, and the stand is checked at each of its six tilt holes.

■ Decision

Table 1. Changes made to the model, the BOM and the calculations (Draft, open for Amish's review).

#	Problem in the concept	Change made	Why this way
P1	The stack sat on a 5 mm "ledge" of no stated material along the two side walls only; the bottom plate had nothing under its high and low edges and nothing under its middle.	A 12 mm plywood base ring (four strips) under the walls, with a 15 mm ledge into the aperture on all four sides. The bottom plate rests on the ledge all round and spans 970 mm between the high and low ledges as ten fin-stiffened strips; the side rails sit directly over the side ledges.	The ribs bring the stack's weight (108 N/m ²) down onto the bottom plate; with its fins bonded it sags about 0.5 mm (1.0 mm on the fins alone), and the whole stack moves together, so the gaps stay at 6 mm (SSK-CAL-001 section 13).
P2	The low wall had four 996 x 2 mm slits for the plate lips, leaving 5.5 mm slivers of plywood that cannot be cut or survive, and a plate with a lip cannot be put through a slit from inside the frame.	The low wall is a comb: a 12 mm sill along the bottom and teeth between eleven open-topped notches 33 mm deep, with a separate cap strip (and its liner) that closes the notches above the stack.	Each plate drops in from above with its tongues in the notches. Lifting the cap lets the plates come out again, which also helps R10.
P3	The brine exit at the low edge was not detailed (R4 at risk): wick tails had to cross the distillate lips, which sit 7.5 mm apart in the same edge.	The plates' low edges are cut to a zigzag. Distillate leaves on six 30 mm tongues at the rib lines and corners, which turn down through slots in the manifold lid. Brine leaves on five 50 mm tongues at the strip centres, each carrying a 30 mm wick tail underneath, over the closed lid and down into the brine gutter. A silicone chevron dam at each brine tongue root turns condensate aside. See A1.	Brine and distillate are separated across the panel's width, not stacked, so every brine path keeps at least 10.5 mm (over the lid) and 44 mm (sideways) from every distillate path.
P4	Nothing stopped the plates and rails sliding down the slope: the lips slid freely in their slits and the plate ends faced soft stone wool.	Two stop blocks, cut from the stage 1 rail polymer, fill the liner's low corners. The plate corners and the rail ends bear on them, and they bear on the low wall.	A hard face where the stack's down-slope load (up to sin 35 deg of its weight) goes into the plywood.
P5	The glazing floated 4 mm below a frame lip with no fixing, in an opening its own size, with no room for the 4.8 mm it grows when hot.	A 1,060 mm square sheet on 3 mm silicone foam tape on the wall tops, held by a mitred aluminium trim (25 x 20 x 2 mm angle) screwed to the walls. The walls end under the tape (52.5 mm tall).	7 mm of room each side for growth; the trim stops 14 mm outside the aperture, so it casts no shade. This adopts item 1 of the 2026-09-26 product model review.
P6	The wicks "drape over the frame wall into the trough", but the wall rises above the stack and the trough had no fixing.	Five feed openings in the high wall, one per wick strip; each tail runs out, up the outside of the wall and over the trough rim. A silicone foam strip on the trough's inner wall closes the openings around the tails. The trough hangs on two fascia gutter brackets screwed to the wall's solid ends.	Feed reaches each stage without crossing anything but the wall; the closure keeps vapor in and dust out.
P7	The manifold and brine gutter had no support or fixing.	Two outlet brackets (30 x 4 mm aluminium flat bar, bent to an L) screwed to teeth of the low wall comb carry the manifold against their uprights and the gutter on their outer ends.	The gutter sits 10 mm lower and 7 mm outboard of the manifold, as the concept requires.
P8	The fins had no fixing and their ends ran into the zigzag edge and the ledge.	Fins 940 mm long, bonded by their 20 mm flange with high-temperature silicone adhesive, 15 mm clear of the ledge.	Bonding leaves the condensing face above unpierced.

#	Problem in the concept	Change made	Why this way
P9	The rear struts were vertical posts from the ground, but the frame's high edge moves about 90 mm along the ground as the tilt changes, and a frame on pinned posts is a mechanism.	Ground frame (two rails, two cross rails); front posts on the rails, made rigid by plywood gussets; an M10 pivot bolt through each post and side wall; fixed-length props (1,000 mm between pins) hinged on blocks near the high end and pinned to the rail at one of six holes (10 to 35 deg in 5 deg steps). The rails run 760 mm behind the pivot.	Each side is a rigid triangle at every tilt. The centre of mass stays at least 260 mm inside the ground frame; the footprint is 1.28 x 1.25 m, within R9.
P10	The walls had no corner joints.	Butt joints, glued and screwed through the side walls; the base ring and the trim tie the corners top and bottom.	Plain joints a home workshop can make.
P11	"Wicks bonded under the plates" gave no method.	Dots of food-grade silicone every 100 mm along both edges of each strip.	Holds the strip without sealing its face; R10 (removal) stays open.
P12	Ribs ran to the plate edge, across the new tongue mouths.	Ribs stop 8 mm short of the tongue tips.	Condensate reaches the distillate tongues unobstructed.

Table 2. Knock-on changes.

Item	Change	Reason
Yield	Wet wick fraction 0.824 to 0.817; design-day yield 10.6 L and gained output ratio 1.26 to 1.34 unchanged at the precision quoted. Low-end vapor loss 25 mL per day (0.2 %).	Wicks stop 13 mm inside the zigzag edge.
Mass	Panel 18.5 kg dry (was 16.7), 22.5 kg wet; stand 8.9 kg. R9 (20 kg dry) still met.	Base ring, trim, tongues, brackets.
Cost	Value-engineering target: USD 355. Estimated cost of the constructable design: USD 416.20 (USD 61.20 over the target); the concept priced at USD 351.20. New BOM lines 15 to 17; lines 2 to 5, 8, 11 and 12 respecified.	Larger plate blanks, trim, stand ground frame, brackets, closure.
Footprint and wind	1.28 x 1.25 m at 10 deg (was 1.28 x 1.16 m); lift equals weight at 18.7 m/s (was 17.5 m/s).	Props sit outside the posts.
Drawings	SSK-DWG-002 Rev P3; making sketches SSK-DWG-101 to 118 added; concept blueprint SSK-DWG-001 Rev P4.	Follow the model.
Documents	SSK-CAL-001 v0.4, SSK-PRC-001 v0.6, SSK-REQ-001 v0.6. R12 is now reported against the value-engineering target; no other requirement changed status.	Follow the model.

Table 3. Proposed, awaiting Amish.

#	Question	Options	Recommendation
A1	How brine leaves the low edge without reaching the distillate (R4; part of the safety case, because brine in the distillate is a drinking-water hazard).	(a) zigzag edges with distillate tongues at the rib lines and brine tongues at the strip centres, as modelled (P3); (b) a cross-wick along the low edge of each stage that carries brine sideways to tails at the side walls; (c) leave the low edge as in the concept and test the brine exit separately at TRL 4.	(a): it keeps the concept's layout (brine over the closed manifold lid into an outboard, lower gutter) and every brine path at least 10 mm from every distillate path. Confirm by measuring each stage's distillate conductivity at TRL 4.
A2	The feed tails leave each wick at the high edge 6 mm above the condensing plate below; if a tail sags or drips there, feed water could reach a condensing face (found in this review; R4, safety case).	(a) accept for the first prototype and measure each stage's distillate conductivity at TRL 4; (b) stagger the plates' high edges about 22 mm per level so each tail leaves clear of the plate below (costs about 4 % of the yield); (c) a 4 mm downturned lip on each condensing plate's high edge.	(a), with (c) as the first fix if the conductivity test shows carryover.

■ Consequences

- `design_state: constructable` in `project.yaml`. The build plan SSK-BLD-001 shows every component and step in pictures generated from the model (`cad/src/build_plan_media.py`), and the design decisions register SSK-DEC-001 lists A1, A2 and the other open items.
- Requirement status is unchanged except that R12 is now reported against the value-engineering target: none not met, six at risk (R2, R4, R6, R7, R8, R10), one not verifiable at TRL 3 (R3), four met on paper (R1, R5, R9, R11), and R12 USD 61.20 over the target.
- The photoreal renders (`media/render-*.png`), `media/card.png` , `media/social-preview.png` and the appearance model `cad/src/product_model.py` still show the concept frame, lips, stand and trough; they need updating on Amish's Mac, where Blender is.
- The plate tongues stay straight until the manifold and gutter are fitted, then are bent by hand (build plan steps 15 and 17).